PROPOSED FOOTWAY TO CONNECT TO EXISTING ROAD

EXISTING 600mm DIA CULVERT

EXISTING HEADWALL OUTLET TO DITCH TO BE REMOVED AND REPLACED WITH A NEW SILT TRAP WITH OUTLET TO NEW CULVERT

FORM OFFLET IN VERGE TO DIRECT RUN OFF TO GULLY

NEW 1.5m WIDE FOOTWAY TO BE CONSTRUCTED OVER CULVERTED DITCH

EXISTING GRASS VERGE TO BE RETAINED 0.75m WIDE

EXISTING DITCH TO BE CULVERTED

EXISTING ACCESS ROAD

CONCRETE PROTECTION TO CULVERT BELOW ROAD

NEW TURNING HEAD AND ACCESS

SHARED DRIVE

NEW SILT TRAP ON NEW CULVERT

HEADWALL OUTLET FROM NEW CULVERT TO EXISTING DITCH

EXISTING DITCH

PLOT 1

PLOT 2

Issues

Cul Mor

Greencroft

Jamestown

Eden Cottage

Thule

Caerhays

Caberfeidh

92.8m

The Highland Council
Comhairle na Gàidhealtachd

Plans, drawings and other material submitted to the local authority are protected by the Copyrights, Designs and Patents Act 1988 (Section 47).

You may only use material which is downloaded and/or printed for consultation purposes, to compare current applications with previous schemes and to check whether developments have been completed in accordance with the approved plans.

Further copies must not be marle without prior permission of the copyright owner.

The Highland Council
Planning & Development Service
APPROVED

KEY

CULVERT

FOOTWAY

GULLY AND TAIL

Drawing No. 2358:102/01 Revision D

	Revisions	Date	Dm
A	LAYOUT REVISED TO REFLECT ARCHITECTS HOUSE LAYOUT	19.04.12	IW
B	REDUCED TO 2 PLOTS. SECTIONS AND CONSTRUCTION DETAILS ADDED.	27.09.12	IW
C	2 PLOT LAYOUT REVISED	16.05.13	IW
D	CULVERT INCREASED TO 600mm	06.09.13	IW

PLANNING DRAWING

MAJOR WHITELAW

JAMESTOWN
2 No. PLOTS

ROAD LAYOUT PLAN

Drawn: DM	Ck'd:	Scale: 1:250 @ A1
Date: DEC 11	Date:	DO NOT SCALE

consulting engineers
hga
HGA(UK) Ltd
Darach House
Stoneyfield Business Park
Inverness IV2 7PA
T: 01463 221717
F: 01463 224575
email: hga@hgagroup.co.uk

Drawing No. 2358:102/01 Revision D